

SN	Reference	Original Clause	Revised Clause with changes highlighted (Deletions are indicated with a strikethrough and additions are indicated by an underline)
1.	Section 6 , Form B, Note , Page 21	<p>Note:</p> <p>1. The Price quoted by the Contractor should be in Indian Currency Only.</p> <p>2. The entire price quoted should include Cost towards Insurance, All Applicable State and Central Taxes and Duties etc.</p> <p>3. The client will not reimburse any other amount over and above quoted by bidder.</p> <p>4. Payment shall be made as per billing schedule mentioned under Payment terms.</p>	<p><u>5. Total cost of work related to part-B should not be lesser than 20% of the contract price (Cost of A + Cost of B)</u></p>
2.	Section 6 6.6.2	<p>Terms of Payment</p>	<p><u>Stage payment percentages mentioned are with reference to Part A cost only. Payment for Part B shall be made in full on completion of Part B work.</u></p>
3.	Section 5, Clause No. 5.2, Part-A, Page 25	<p>AT TOYODA GOSEI MINDA INDIA PLANT :</p> <p>1. The two 11 KV underground cable running from 1 MW Solar Plant to Mikuni India plant is to be rerouted to the Toyoda Gosei 11 KV breaker room by splicing the cable at about 5-10 metres (Point D) from the Toyoda Gosei breaker room (as shown in the satellite image above) including required trenching / civil works.</p>	

SN	Reference	Original Clause	Revised Clause with changes highlighted (Deletions are indicated with a strikethrough and additions are indicated by an underline)
		<p>2. Checking and Servicing of the RMU (removed from Mikuni Plant and installed at Toyoda) inside 11KV HT breaker room of Toyoda Gosei .</p> <p>3. Termination of both the 11 KV HT cable in the RMU.</p> <p>4. Supply & Installation of the 11 KV HT MIP Meter box as per JVVNL norms.</p> <p>5. 11 KV CT / PT as per JVVNL Norms with CTL tested with control wiring complete.</p> <p>6. Interconnection between RMU, Meter box and breaker of Toyoda Gosei.</p> <p>7. All civil and mechanical works related to the cable, meter box installation.</p> <p>8. Preparation and approval (by relevant agencies) of all drawings related to civil, mechanical and electrical works</p> <p>9. CEIG approval for the interconnection to Toyoda Gosei & coordination / approval of JVVNL</p>	<p>4. Supply & Installation of the 11 KV HT MIP <u>Meter and Meter box</u> <u>in the scope of contractor as per JVVNL norms.</u> <u>In case the meter with CT/PT is to be supplied by JVVNL then the amount paid by DNSPCL if any will be recovered from the Invoice of the contractor.</u></p>